



4000 Holland Blvd.  
Chesapeake, VA 23323

6899 Phillips Industrial Blvd  
Jacksonville, FL 32256



Industrivej 23  
DK-Karup, Denmark

**TECHNICAL NEWS BULLETIN**  
**VOLUME FOUR**  
**May 26, 2009**

---

**New IBV KITS!!!**

The new IBV kits are ready to go! Several improvements have been made to the IBV kits that should make architects, builders and homeowners very happy!

There are a few changes that should be noted when ordering the new IBV kits:

**1)** Earthcore Industries has incorporated an in-line damper into the downdraft diverter for our IBV Series. There is a lever located on the back side of the lintel which will be manually opened and closed. A micro-switch inside the lintel connected to the damper lever will not allow the fire logs to ignite when the damper is in the closed position.

**2)** The lintel is very similar to the older design and will slide on to the smoke dome assembly as before. The ends are perforated for easy cutting to the shorter 36" length depending on the box size. No cutting is necessary for the 46" IBV. The 36" will require cutting on one side of the front, and a cut on the rear of the lintel. **Cut only on the perforated edges provided!**

**3)** The kits will come in **two (2) boxes as before**, box 1 of 2 and 2 of 2.

Should you need either of the boxes separately for whatever reason, you can still order each box individually as before. The new parts will be in each box respectively. The Junction assembly will still be ordered separately as before; also it will be shipped separately from Earthcore and is **not** a part of the kit part number.

**4)** The instruction manual will be located in box 1 of 2, supplied by Lennox.

Please feel free to contact the Technical Department if you have any questions or need additional information!